Hotel FF&E BOQ Template

Eighteen columns that make a bill of quantities quotable, inspectable and freight-ready. Most disputes at handover trace back to a column that was missing at tender.

Version 1.0 · Last reviewed 3 November 2026 · foshanFFE.com

> **Why the columns matter.** A BOQ with description, quantity and price is an enquiry. A BOQ with drawing revision, material, finish reference, compliance standard and packing data is a purchase order waiting to be signed. The difference is about two hours of work at tender and several weeks of argument at handover.

The eighteen columns

Column	Why it belongs in the BOQ	Example entry
Item no.	Sequential, and never reused when a line is deleted. The number is the audit trail.	GR-01
Room type / area	Guestroom king, suite, lobby, F&B. Drives packing marks and installation sequence.	Guestroom King
Location code	Floor and room range the item belongs to.	L3–L9, 301–420
Description	What it is, in the designer's language, not the factory's.	Nightstand, 2-drawer, open shelf
Drawing / spec reference	The revision that governs. A line without a revision is a future dispute.	FFE-204 rev C
Quantity	Per room type and total. Both columns, always.	1 per room / 120
Dimensions (mm)	W × D × H. State whether the height includes the top or the leg.	600 × 450 × 550
Primary material	Substrate plus finish, named. “Wood” is not a material specification.	Oak veneer, MDF core, E1
Finish / colour	Reference to the approved sample or a named standard, not “as photo”.	Sample F-07, matt 5°
Fabric / leather	Name, composition, Martindale or Wyzenbeek result, fire treatment.	Grade C, 40k Martindale, BS 5852
Hardware	Brand or equivalent, function, finish. Soft-close stated explicitly.	Blum soft-close, nickel
Electrical	Voltage, plug type, socket positions, switching, listing required.	220–240V, UK, UL optional
Compliance	Which standard applies and who must hold the evidence.	CARB P2 / BS 5852 / CE DoC
Unit price	Ex-works, itemised. Freight and packing priced separately.	USD 148.00
Lead time	Days from sample approval, not from enquiry.	50 days
Packing	Carton type, units per carton, volume, gross weight.	1 pc/ctn, 0.28 m^3, 34 kg
HS code	Six digits minimum. Wrong code, wrong duty.	9403.50
Notes	Anything the factory must know that has no column.	Left-hand drawer lockable

What a completed line looks like

Seven lines from a 120-key project, trimmed to the columns that carry the most weight. Note that the lead time runs from sample approval, not from the enquiry date.

Item	Room type	Location	Description	Drawing	Qty	Dimensions	Unit price	Lead time	HS code
GR-01	Guestroom King	L3–L9	Nightstand, 2-drawer	FFE-204 rev C	1 / 120	600×450×550	USD 148	50 days	9403.50
GR-02	Guestroom King	L3–L9	Headboard, upholstered	FFE-205 rev B	1 / 120	1800×120×1100	USD 210	55 days	9403.50
GR-03	Guestroom King	L3–L9	Wardrobe, 2-door + safe	FFE-206 rev C	1 / 120	1200×600×2200	USD 395	60 days	9403.50
SU-01	Junior Suite	L8–L9	Sofa, 2-seat	FFE-311 rev A	1 / 24	1600×850×780	USD 520	55 days	9401.61
LB-01	Lobby	L1	Lounge chair, contract	FFE-402 rev B	12 / 12	720×780×760	USD 285	50 days	9401.61
FB-01	All-day dining	L1	Dining chair, timber frame	FFE-501 rev C	180 / 180	480×520×820	USD 96	45 days	9401.69
OD-01	Pool terrace	L1	Sun lounger, powder-coated	FFE-601 rev A	40 / 40	2000×700×350	USD 178	45 days	9401.79

The five things buyers leave out, and what they cost

Omission	What it costs later
Drawing revision	The factory prices the drawing it was given. If the design moved and nobody reissued, you buy the old version twice.
Finish reference	“As sample” without a sample number means every batch is judged against memory. Colour drift across floors follows.
Fire and formaldehyde standard	Discovered at customs or at brand audit, when the goods already exist and the replacement lead time is the whole schedule.
Packing and volume	Freight is quoted on an estimate, the container is short, and the balance ships as LCL at three times the unit cost.
HS code	Wrong code, wrong duty, and a customs query that stops the container while the installation crew waits.

Order of work

1. **Freeze the design revision.** Publish the revision number that governs the BOQ. Every later change is a written variation, not a conversation.
2. **Split by room type, then by category.** Room type drives packing and installation; category drives which factory quotes.
3. **Price ex-works, then add packing, then freight.** One blended price hides the only three numbers you can actually negotiate.
4. **State lead time from sample approval.** Any other start point makes the number unfalsifiable.
5. **Attach the compliance column before tender, not after award.** It changes which factories can bid, and it is cheaper to learn that early.

Blank sheet header

Item no.	Room type / area	Location code	Description	Drawing / spec ref	Qty per room	Total qty	Dimensions	Material	Finish	Fabric	Hardware	Electrical	Compliance	Unit price	Lead time	Packing	HS code

Send a completed sheet and you get a costed response, or the questions needed to produce one: **foshanFFE.com** · one purchase order, one inspection calendar, one document index.